

MUNITION STORAGE IGLOOS


STANDARD DETAIL DRAWINGS

INDEX

DWG. NO.	SH. NO.	DESCRIPTION
AD 00-00-00	1	INDEX


DWG. NO.	SH. NO.	DESCRIPTION
MAGAZINE, STRADLEY TYPE (30'-0" SPAN)		
00-00-00	1	INDEX
33-15-03	S-1	DRAINAGE PLAN, SECTION, AND MISC. DETAILS
33-15-03	S-2	ARCH. & MISC. DETAILS
33-15-03	S-3	PORTAL WALL PLAN, ELEV. & DETAILS
33-15-03	S-4	PORTAL WALL SECTIONS
33-15-03	S-5	BLAST DOOR, PLAN & SECTIONS
33-15-03	S-6	MISC. BLAST DOOR DETAILS
33-15-03	E-1	ELECTRICAL PLAN & DETAILS - SHEET NO. 1
33-15-03	E-2	ELEC. PLANS & DETAILS - SHEET NO. 2
33-15-03	E-3	INTERIOR LIGHTING & MISC.
33-15-03	E-4	EXTERIOR ELECTRICAL - SHEET 1
33-15-03	E-5	EXTERIOR ELECTRICAL - SHEET 2

DWG. NO.	SH. NO.	DESCRIPTION
MAGAZINE, STEEL, OVAL ARCH. (31'-2" SPAN)		
33-15-04	S-1	PLAN AND SECTIONS
33-15-04	S-2	PORTAL WALL - PLAN, ELEV. & DETAILS
33-15-04	S-3	PORTAL WALL - SECTIONS
33-15-04	S-4	MISCELLANEOUS DETAILS
33-15-04	S-5	PLAN AND SECTIONS
33-15-04	S-6	MISC. BLAST DOOR DETAILS
33-15-04	E-1	ELECTRICAL PLAN & DETAILS - SHEET NO. 1
33-15-04	E-2	ELEC. PLANS & DETAILS - SHEET NO. 2
33-15-04	E-3	INTERIOR LIGHTING & MISC.
33-15-04	E-4	EXTERIOR ELECTRICAL - SHEET 1
33-15-04	E-5	EXTERIOR ELECTRICAL - SHEET 2






DATE	DESCRIPTION	MADE	APPRO'D
REVISIONS			
U. S. ARMY ENGINEER DISTRICT, OMAHA CORPS OF ENGINEERS OMAHA, NEBRASKA			
DESIGNED BY:	MUNITION STORAGE IGLOOS INDEX <i>adest</i> 347-78-48(26)		
DRAWN BY:			
CHECKED BY:			
SUBMITTED BY:			
CHIEF SECTION:			
RECOMMENDED:	APPROVED:	DATE:	JULY 1978
CHIEF DESIGN BRANCH:	CHIEF ENGINEERING DIVISION	SCALE: AS SHOWN	SPEC. NO. DAC445
APPROVED:	DRAWING NUMBER		00-00-00
CCL. C. E., DISTRICT ENGINEER			SHEET 1

THIS PLAN ACCOMPANIES CONTRACT NO. DAC445 MODIFICATION NO.



- LEGEND:**
- (A) (B) (D) 200W ceiling mount incandescent luminaire suitable for use in Class I, Division I, Group C hazardous areas, in Class II, Division I, Group G hazardous areas, or in nonhazardous environments, respectively. See Sh. E 3
 - (H) (a) (L) (b) (K) 100W ceiling mount high pressure sodium luminaire suitable for use in Class I, Division I, Group C hazardous areas, in Class II, Division I, Group G hazardous areas, or in nonhazardous environments, respectively. See Sh. E 3, Small letters denote switching arrangement.
 - (E) (F) (G) Surface mounted exterior luminaire - 70W high pressure sodium (HPS), 35 W low pressure sodium (LPS), or 250W quartz iodine respectively. See sheets E 4 and E 5
 - ⊖ Duplex convenience outlet, weatherproof.
 - ⊕ Junction box, cast metal with threaded walls or hubs.
 - Conduit run. Note: Any conduit run not otherwise indicated contains two No. 12 AWG. (3.3 sq. mm) wires in a 1/2 in. (12.7mm) conduit. A greater number of wires are shown with cross lines as follows.
 - The long cross line identifies the grounded (neutral) conductor and the short cross lines identify the phase conductors. Unless otherwise indicated, all conductors are No. 12 AWG. (3.3 sq. mm).
 - Auxiliary empty rigid steel conduit run concealed or installed 2'-0" below finished grade. Sized as indicated.
 - Conduit terminated with a plugged coupling.
 - Secondary surge arrester (S. A.), 650 V, weatherproof housing.
 - ⊙ Lightning air terminal. Extend 2'-0" (61) above protected object.
 - Ground rod.
 - Facility counterpoise system, No. 1/0 AWG. (53.5 sq. mm) bare copper wire.
 - Unless otherwise indicated, the parenthetic metric dimensions shown are in centimeters and are minimum acceptable.
 - 6" x 6" x 4'-0" (min.) NEMA 3R wireway.
 - WP5a Weatherproof switch 125 V, 20A. Letter "a" denotes switching arrangement.


- NOTES:**
1. The conduit system on the front of structure is to have supports spaced not more than 8'-0" (243.8) supports on each side of construction joints shall not exceed 5'-0" (152).
 2. Running thread coupling connections are not permitted for the rigid conduit systems. All boxes are to be cast type.
 3. For the 120/240 volt, single phase, 3-wire service; install conduit 2'-0" (61) below finished grade and terminate with a plugged coupling not less than 5'-0" (152) beyond paved area. Service pole by others shall not be less than 50 ft. (15.2m) from the structure(s). Preferred arrangement is to install the main service disconnect means on a power or service pole located within 50 ft. (15.2m) of the structure(s) (or 100 ft. max.) However, if the electrical service and distribution will not be installed as a part of this project, the main disconnect shall be located on the exterior walls of the center structure(s). See details.
 4. For future installation by others of a telephone type cable, install conduit with a pull wire, 2'-0" (61) below finished grade and terminate with a plugged coupling not less than 5'-0" (152) beyond paved area.
 5. If pad mounted transformers are used, minimum size will be 15 KVA.
 6. For door well heating cable, wattage capacity and number of loops shall be as required. The hot sections of the cable shall be extended the full length of the door.
 7. Circuit breakers and panelboard shall have an interrupting capacity of 10,000 symmetrical amps min.
 8. Thermostat control shall energize the door well heaters when the outside temperature is below 32°F and de-energize the Doorwell heaters when the outside temperature is above approximately 37°F. Thermostat enclosure shall be weatherproof.
 9. All wire and conduit sizes assume use of copper conductors and 75°C rated insulation.
 10. For exterior lighting details see sheets E 3 - E 5.




- APPLICATION NOTES:**
1. Details, notes, plans, etc. on these sheets shall be deleted, crossed out, or modified as required to fit specific applications.
 2. Selection of single or multiple igloo format should be carefully evaluated. Conduit should be provided under concrete paving if the installation of future igloos alongside would be probable.
 3. For some applications having low soil conductivity, the counterpoise systems of individual scattered igloos may have to be interconnected.
 4. Three different lighting arrangements are available:
Scheme I - incandescent source for interior lighting, quartz iodine for exterior; Scheme II - incandescent interior, HPS or LPS exterior; Scheme III - HPS interior, HPS or LPS exterior. Because of energy considerations, Scheme III is preferred. If instant start operation or color discrimination is critical, Scheme I or II could be utilized. See sheets E 3 - E 5.
 5. Conductor size of feeders is governed by voltage drop (3% max.) considerations rather than ampacity. No derating will be necessary in segment "a".
 6. Columns in the feeder and service schedules contain ratings, sizes, loads pertaining to lighting schemes I, II, and III. The inapplicable figures should be deleted in accordance with the scheme selected.
 7. For some applications, only 2 or 3 igloos may be involved; however, since additional structures may be added later, the conduit sizes in the feeder Schedule should not be reduced without specific approval.
 8. Equipment within the structure must be suitable for the specific hazardous classification. See Application Note 2 on Sh. E 3.
 9. Sizing of feeders for the multi-igloo arrangement is valid for a spacing of 130 ft. max., center to center. Sizes should be adjusted as required if the facewall width or spacing exceeds this.

DATE	DESCRIPTION	MADE	APPROV
REVISIONS			
U. S. ARMY ENGINEER DISTRICT, OMAHA CORPS OF ENGINEERS OMAHA, NEBRASKA			
DESIGNED BY:	JES/OLV		
DRAWN BY:	T.S.A.		
CHECKED BY:			
SUBMITTED BY:			
CHIEF ELEC. FAC. SECTION			
RECOMMENDED:			
APPROVED:			
CHIEF DESIGN BRANCH			
CHIEF ENGINEERING DIVISION			
SCALE: AS SHOWN			
SPEC. NO. DCA445			
DATE	347-78-48 (33)		
DRAWING NUMBER	35-15-03		
SHEET E-1			



THIS PLAN ACCOMPANIES CONTRACT NO. DCA445 MODIFICATION NO.





ONE LINE DIAGRAM
120/240 VOLT MULTIPLE IGLOO SERVICE

Note: See service schedules for size of material and equipment not shown.



MAIN SERVICE SCHEDULE
(See Application Notes 4, 6, 7 & 5 Sh. E-1)


Transformer Size (KVA) (A, B) / (C)	Number of Igloos	Load (KW) (1)²/(11)²/(111)²	Fusible Disconnect Switch Size	Fuse Size (Amps)	Conductor Size (AWG)	Conduit Size (Inch)
5	1	5.0/4.7/3.3**	30/30/30	30/30/20	#8/ #8/ #8	1/ 1/ 1
10	2	10.0/9.4/6.6	60/60/60	60/60/40	#6/ #6/ #6	1/ 1/ 1
15	3	15.0/14.1/9.9	100/100/60	90/90/60	#3/ #3/ #4	1 1/2/ 1 1/2
25	4	20.0/18.8/13.2	200/200/100	125/110/80	#1/ #2/ #3	1 1/2/ 1 1/2
25/25/25	5	25.0/23.5/16.5	200/200/100	150/150/100	#1/0/ #1/0/ #2	1 1/2/ 1 1/2
37 1/2/30/25	6	30.0/28.2/19.8	200/200/200	175/175/125	#3/0/ #2/0/ #1	2 1/2/ 1 1/2
37 1/2/37 1/2/30	7	35.0/32.9/23.1	400/200/200	225/200/150	#4/0/ #3/0/ #1/0	2 1/2/ 1 1/2

** See Application Note 6
** If structure is single igloo format rather than multiple these figures would be 5.5/4.9/3.5



FEEDER SCHEDULE
(See Notes 4, 7 & 9 on Sh. E-1)

To Igloo (Number)	Approx. Distance (Feet)	Load (KW) (1)²/(11)²/(111)²	Circuit Breaker Rating (Amps)	Conductor Size (AWG)	Conduit Size (Inches) Segment **
2(R)	105	5.0/4.7/3.3	30 / 30 / 30	#6/ #6/ #8	2 --- ---
3(L)	105	5.0/4.7/3.3	30 / 30 / 30	#6/ #6/ #8	2 --- ---
4(R)	210	5.0/4.7/3.3	30 / 30 / 30	#4/ #4/ #6	--- 1 1/2 ---
5(L)	210	5.0/4.7/3.3	30 / 30 / 30	#4/ #4/ #6	--- 1 1/2 ---
6(R)	315	5.0/4.7/3.3	30 / 30 / 30	#3/ #3/ #4	--- --- 1 1/2
7(L)	315	5.0/4.7/3.3	30 / 30 / 30	#3/ #3/ #4	--- --- 1 1/2


** See Application Note 6
** See Application Note 7



GROUNDING SYSTEM
(NO SCALE)



DETAIL A
NO SCALE






- GROUNDING NOTES**
- #10 Bare stranded copper conductor, 3'-0" to 8'-0" from foundation, 2'-6" below finished grade.
 - 3/4" x 10'-0" Copper clad ground rod.
 - Connection of thermo or thermo chemical type.
 - #8 Bare stranded copper conductor
 - #8 Bare stranded copper conductor and 1/2" conduit

APPROX. DEMAND - LOAD PER UNIT

Lighting (Watts)	Receptacles (Watts)	Door Heater Cable (Watts)	Approx. Total (KW)
Exterior*	Interior		
Scheme I - Quartz iodine / Incandescent			
500 (1000)	1500	200	2500± 5.0 (5.5)
Scheme II - HPS/ Incandescent			
190 (380)	1800	200	2500± 4.7 (4.9)
Scheme III - HPS/ HPS			
190 (380)	390	200	2500± 3.3 (3.5)

*Table is for multiple type Igloos; figures in parenthesis are for single Igloos.



DATE	DESCRIPTION	MADE	APPR'D

REVISIONS


U. S. ARMY ENGINEER DISTRICT, OMAHA
CORPS OF ENGINEERS
OMAHA, NEBRASKA

DESIGNED BY: JES/DLV
DRAWN BY: S.A.M.-A.J.A.
CHECKED BY: B.N.H.
SUBMITTED BY:
CHIEF ELEC. FAC. SECTION
RECOMMENDED:
CHIEF DESIGN BRANCH
APPROVED:
CHIEF ENGINEERING DIVISION
DATE: 3-7-78-48(34)

MUNITION STORAGE IGLOOS
MAGAZINE, STRADLEY TYPE,
(30'-0" SPAN) EARTH-COVERED
ELEC. PLANS & DETAILS - SHT. NO. 2

THIS PLAN ACCOMPANIES CONTRACT NO. DACA45
MODIFICATION NO.

COL. C. E., DISTRICT ENGINEER
SHEET E-2
33-15-03



CANDLEPOWER TABLE
LUMINAIRE "H"
100 W HPS

Vertical Angles	C of E Format	Horizontal Angles		
		(180) 270	(180) 0	(180) 90
0	IES Format	180	90	0
0	90	25	25	25
5	85	100	100	100
10	80	200	200	200
15	75	330	330	330
20	70	550	550	550
25	65	880	880	880
30	60	1200	1200	1200
35	55	1485	1485	1485
40	50	1605	1605	1605
45	45	1730	1730	1730
50	40	1870	1870	1870
55	35	1980	1980	1980
60	30	2120	2120	2120
65	25	2280	2280	2280
70	20	2330	2330	2330
75	15	2390	2390	2390
80	10	2365	2365	2365
85	5	2340	2340	2340
90	0	2375	2375	2375

Avg. Candlepower = 1481.8 Candela

CANDLEPOWER TABLE
LUMINAIRE "I"
100 W HPS

Vertical Angles	C of E Format	Horizontal Angles		
		(180) 270	(180) 0	(180) 90
0	IES Format	180	90	0
0	90	275	275	275
5	85	385	385	385
10	80	440	440	440
15	75	770	770	770
20	70	1100	1100	1100
25	65	1285	1285	1285
30	60	1385	1385	1385
35	55	1495	1495	1495
40	50	1620	1620	1620
45	45	1740	1740	1740
50	40	1880	1880	1880
55	35	1950	1950	1950
60	30	1935	1935	1935
65	25	1850	1850	1850
70	20	1750	1750	1750
75	15	1650	1650	1650
80	10	1565	1565	1565
85	5	1512	1512	1512
90	0	1540	1540	1540

Avg. Candlepower = 1375.1 Candela

CANDLEPOWER TABLE
LUMINAIRE "K"
100 W HPS

Vertical Angles	C of E Format	Horizontal Angles		
		(180) 270	(180) 0	(180) 90
0	IES Format	180	90	0
0	90	5	5	5
5	85	35	35	35
10	80	65	65	65
15	75	100	100	100
20	70	155	155	155
25	65	260	260	260
30	60	700	700	700
35	55	1455	1455	1455
40	50	2080	2080	2080
45	45	2305	2305	2305
50	40	2320	2320	2320
55	35	2190	2190	2190
60	30	2090	2090	2090
65	25	1980	1980	1980
70	20	1855	1855	1855
75	15	1735	1735	1735
80	10	1640	1640	1640
85	5	1745	1745	1745
90	0	1880	1880	1880

Avg. Candlepower = 1294.5 Candela

HIGH PRESSURE SODIUM (HPS) LUMINAIRE :

The fixture shall be an explosionproof type rated for use in Class I, Division I, Group C hazardous areas, a dustproof type rated for use in Class II, Division I, Group G hazardous areas, or an industrial type low bay unit suitable for nonhazardous areas as indicated. Each unit shall have the following features:

The housing and all exposed parts and hardware shall be formed from non-corroding materials or shall have corrosion-resistant finishes. The assembly, or separate adaptors or boxes, must be suitable for mounting to a concrete ceiling. The wiring entrance shall accommodate 3/4 in. threaded conduit.

A heat and shock resistant glass diffuser (globe, lens, refractor) is to be furnished. It must have a prismatic surface to provide controlled light distribution and minimal glare. A prismatic polycarbonate diffuser will be acceptable for the industrial type of luminaire.

The reflector for explosionproof or dustproof fixtures must be dome type of either porcelain enameled steel or reinforced fiberglass construction. For the industrial type luminaire an arrangement consisting of either a polished or anodized aluminum reflector or a prismatic glass/metal reflector combination will be acceptable without a diffuser.

Cast metal guards are to be included on explosionproof units, wire guards are acceptable on dustproof units.

The lampholder, ballast, and wiring shall be suitable for operation at the ambient temperatures applicable for the particular hazardous classification (for the industrial fixture - normal lamp operating temperature plus 104° F (40° C) externally). The socket should be shock absorbing type (luminaire "H" and "I").

The ballast is to be a high power factor type (over 90%) rated for operation at -20° F (-29° C) or lower and under a +10% line variation with the resultant change in lumen output (lamp wattage) not to exceed +12%.

A 100 watt lamp shall be furnished with each unit (LUI00/BD, LUI00/BU, LUI00, or C100 as applicable).

The unit should provide photometric performance characteristic of IES Type V distribution as indicated in the candlepower table when the unit is operated at rated voltage of 120V nominal.

INCANDESCENT LUMINAIRE :

The fixture shall be an explosionproof type rated for use in Class I, Division I, Group C hazardous areas, a dustproof type rated for use in Class II, Division I, Group G hazardous areas, or an industrial type, low bay unit suitable for nonhazardous areas as indicated. Each unit shall have features as specified on Corps of Engineers drawing series 40-06-04, sheet 8B, 8A, or 3 respectively.




A 200 watt lamp shall be furnished with each unit.

APPLICATION NOTES:

- Data and details on this sheet should be deleted, crossed out, or modified as required for a specific application.
- Unless the criteria furnished for design of a particular facility has stipulated a Class II environment, the data pertaining to Class I luminaires shall be utilized. The nonhazardous fixture shall not be used unless written authorization has been furnished by the responsible officials.
- The arrangement shown will provide an average illumination level, horizontally measured, of approximately 5 footcandle (54 lux) on a 3 ft. work plane. If somewhat higher levels are required, a 300 W. incandescent (PS30, 6110 lumens) or a 150 W. HPS (16000 lumens) unit could be used. Illumination and candlepower would be raised by a factor of 1.52 or 1.68 respectively (lumens new unit/lumens original unit). Wiring and conduit sizes would also have to be adjusted.

NOTES:

- Catalog literature and photometric data for proposed luminaires shall be furnished to the Contracting Officer for review (see specs). Photometric data should identify the candlepower distribution pattern characteristic of the luminaire in either a tabular format as shown or a curve/graph format. To be considered equivalent photometrically, the average value of candlepower of the proposed luminaire must be 90% or more of the average noted under the candlepower table shown on this sheet.
- The values listed in the candlepower table are for fixtures without guards. Cast guards will reduce the candlepower (and thus illumination) approximately 7-12% on the average for luminaire "A", "H", or "I". The wire guard would cause a reduction of 1% approximately.
- Spare lamps in an amount equivalent to not less than 5% of the total number of luminaires installed in the project shall be delivered to the Contracting Officer.



CANDLEPOWER TABLE
LUMINAIRE "A"
200 W INCANDESCENT

Vertical Angles	C of E Format	Horizontal Angles		
		(180) 270	(180) 0	(180) 90
0	IES Format	180	90	0
0	90	0	0	0
5	85	120	120	120
10	80	160	160	160
15	75	320	320	320
20	70	360	360	360
25	65	400	400	400
30	60	440	440	440
35	55	480	480	480
40	50	530	530	530
45	45	570	570	570
50	40	630	630	630
55	35	670	670	670
60	30	750	750	750
65	25	780	780	780
70	20	750	750	750
75	15	720	720	720
80	10	740	740	740
85	5	750	750	750
90	0	770	770	770

Avg. Candlepower = 523.2 Candela

CANDLEPOWER TABLE
LUMINAIRE "B"
200 W INCANDESCENT

Vertical Angles	C of E Format	Horizontal Angles		
		(180) 270	(180) 0	(180) 90
0	IES Format	180	90	0
0	90	0	0	0
5	85	20	20	20
10	80	120	120	120
15	75	240	240	240
20	70	390	390	390
25	65	360	360	360
30	60	360	360	360
35	55	450	450	450
40	50	510	510	510
45	45	630	630	630
50	40	750	750	750
55	35	870	870	870
60	30	720	720	720
65	25	740	740	740
70	20	800	800	800
75	15	890	890	890
80	10	910	910	910
85	5	930	930	930
90	0	1020	1020	1020

Avg. Candlepower = 563.7 Candela

CANDLEPOWER TABLE
LUMINAIRE "D"
200 W INCANDESCENT

Vertical Angles	C of E Format	Horizontal Angles		
		(180) 270	(180) 0	(180) 90
0	IES Format	180	90	0
0	90	0	0	0
5	85	10	10	10
10	80	65	65	65
15	75	165	165	165
20	70	395	395	395
25	65	535	535	535
30	60	620	620	620
35	55	700	700	700
40	50	750	750	750
45	45	820	820	820
50	40	875	875	875
55	35	945	945	945
60	30	975	975	975
65	25	995	995	995
70	20	1020	1020	1020
75	15	1040	1040	1040
80	10	1085	1085	1085
85	5	1105	1105	1105
90	0	1110	1110	1110

Avg. Candlepower = 695.3 Candela

LUMINAIRE PARAMETERS

Luminaire	A	B	D	H	I	K
Lamp Type	200W/A25	200W/PS30	200W/A25	LUI00	LUI00	LUI00
Rated Life (hours)	750	750	750	12000	12000	12000
Initial Lumens	4010	3710	4010	9500	9500	9500
Input Watts	210	200	200	130	130	130
Maint. Factor	0.70	0.70	0.65	0.70	0.70	0.65
Coef. of Util.	0.53	0.57	0.59	0.61	0.60	0.66°
Corps of Engrs. Dwg. Series 40-06-04	Sh. 8 B	Sh. 8 A	Sh. 3	---	---	---

°0.66 for reflector units; 0.48 refractor types; 0.62 combination reflector-refractor types

METRIC EQUIVALENTS

CABLE			CONDUIT		
U. S. (AWG) (kcm)	Exact. Equiv. (mm ²)	Capacity Equiv. + (mm ²) ±	U. S. (inch)	Exact. Equiv. (mm)	Standard Size (mm)
12	3.3	2.5	---	---	11
10	5.3	4	1/2	12.7	13.5
8	8.4	10	---	---	16
6	13.3	16	3/4	19.1	21
4	21.1	25	1	25.4	29
3	26.6	25	1-1/4	31.8	36
2	33.6	25*	1-1/2	38.1	42
1	42.4	35	2	50.8	48
1/0	53.5	50*	3	76.2	---
2/0	67.4	50*	3	76.2	---
3/0	85.0	70*	3	76.2	---
4/0	107	95	3	76.2	---
250	127	95*	3	76.2	---
300	152	120	3	76.2	---
350	173	120*	3	76.2	---
500	253	150*	3	76.2	---
600	304	185*	3	76.2	---

Conversions:
1 inch = 25.4 mm
1 kcm = 0.5067 mm²
1 foot = 0.3048 m
1 f.c. = 10.76 lux

+ Standard metric sizes equiv. to 60°C. U. S. Cable
± Standard metric sizes equiv. to 75°C. U. S. Cable
* Ampacity is within 10% of U. S. value
(Based on 1978 NEC and 1974 German code)



U. S. ARMY ENGINEER DISTRICT, OMAHA
CORPS OF ENGINEERS
OMAHA, NEBRASKA


DESIGNED BY: D L V
DRAWN BY: T S A
CHECKED BY:
SUBMITTED BY:
CHIEF ELEC. FAC. SECTION
RECOMMENDED:
CHIEF DESIGN BRANCH

MUNITION STORAGE IGLOOS
MAGAZINE, STRADLEY TYPE
(30'-0" SPAN) EARTH COVERED
INTERIOR LIGHTING & MISC


APPROVED: [Signature]
DATE: 3-7-78
SCALE: AS SHOWN
SHEET NO. 33-15-03
SHEET E-3

CDL C. E. DISTRICT ENGINEER


THIS PLAN ACCOMPANIES CONTRACT NO. DACA45 MODIFICATION NO.



STYLE I
EPA=1.12



STYLE II
EPA=1.12



STYLE III
EPA=1.52

CANDLEPOWER TABLE - LUMINAIRE "E"
70 WATT HIGH PRESSURE SODIUM


		Horizontal Angles																			
Corps Format	IES Format	(265)	(255)	(245)	(235)	(225)	(215)	(205)	(195)	(185)	(175)	(165)	(155)	(145)	(135)	(125)	(115)	(105)	(95)	90	
		185	195	205	215	225	235	245	255	265	275	285	295	305	315	325	335	345	355	360	
0	90	3	3	11	23	38	56	93	113	131	149	263	359	549	711	843	812	677	579	591	
5	85	3	3	12	26	44	68	113	135	155	282	455	683	1023	1395	1512	1418	1188	1043	1070	
15	75	6	6	17	30	50	75	107	147	213	569	798	930	1202	1341	1463	1389	1194	1067	1038	
25	65	21	23	30	44	65	95	134	192	278	498	567	878	1133	1278	1415	1230	1053	999	978	
35	55	39	41	53	71	105	153	219	294	432	509	621	674	906	1274	1239	1134	966	909	888	
45	45	69	77	96	126	183	251	330	413	542	618	573	525	656	914	927	785	761	720	708	
55	35	129	146	180	231	297	368	458	569	638	645	597	548	528	591	659	696	711	723	717	
65	25	240	255	302	354	425	498	575	609	650	657	639	605	567	537	534	555	569	569	569	
75	15	387	395	422	453	498	534	572	605	630	644	647	644	623	594	576	558	554	549	551	
85	5	510	506	513	518	528	540	546	561	567	575	579	584	584	585	587	591	594	594	594	
90	0	557	554	557	554	557	555	557	557	558	560	560	560	560	560	558	560	560	561	561	

Average Candlepower = 525.7 Candela

CANDLEPOWER TABLE LUMINAIRE "F"
35 WATT LOW PRESSURE SODIUM

		Horizontal Angles																			
Corps Format	IES Format	(265)	(255)	(245)	(235)	(225)	(215)	(205)	(195)	(185)	(175)	(165)	(155)	(145)	(135)	(125)	(115)	(105)	(95)	90	
		185	195	205	215	225	235	245	255	265	275	285	295	305	315	325	335	345	355	360	
5	85	0	0	4	16	34	71	83	56	97	217	286	303	300	290	313	365	404	412	412	
15	75	0	0	2	9	18	35	72	119	123	185	343	443	459	413	435	532	664	715	722	
25	65	13	14	16	21	29	51	103	147	150	238	375	501	565	619	707	811	899	923	934	
35	55	25	27	28	37	53	94	133	168	184	282	397	504	615	765	859	933	994	1014	1026	
45	45	44	44	52	79	118	158	182	203	222	313	425	535	644	763	874	961	1010	1032	1043	
55	35	128	144	174	208	236	265	281	286	301	374	483	598	694	785	870	941	990	1020	1024	
65	25	344	342	344	352	354	360	351	351	379	446	527	635	723	800	859	896	928	948	954	
75	15	400	395	391	390	388	384	380	400	437	478	521	573	625	680	724	747	774	788	790	
85	5	410	411	413	417	425	436	450	465	476	490	504	523	537	547	553	557	562	564	562	
90	0	481	481	481	481	481	481	481	481	481	481	481	481	481	481	481	481	481	481	481	

Average Candlepower = 431.0 Candela



Values shown above pertain to right hemisphere. The left half of the luminaire is symmetrical.

WALL MOUNT LUMINAIRE:

The unit shall be a heavy duty weatherproof type constructed of die cast aluminum. Style I, II, or III may be furnished at the Contractor's option. Each unit shall have the following features:

The housing and all exposed parts and hardware shall be formed from non-corroding materials or shall have corrosion-resistant finishes.

The assembly must have provisions for mounting on a concrete or sheet steel surface. The back portion of the housing shall be tapped to accommodate threaded conduit of 3/4 in. min.

Access for relamping or for gasket or ballast replacement is to be by means of a hinged door or cover. If bottom hinged, a metal safety strap, cable, or retaining chain must be included.

A tempered heat and impact resistant borosilicate glass diffuser is to be furnished. It must have a prismatic surface to provide controlled light distribution and minimal glare. A vandal resistant, prismatic polycarbonate (Lexan or equal) diffuser may be substituted at the Contractor's option.

The reflector must be formed from an aluminum sheet, either Alzak or anodized to an asymmetric contour.

The lampholder, ballast, and wiring shall be suitable for operation at high ambient temperatures (normal lamp operating temperature internally plus 110°F (43°C) ambient externally).

The ballast is to be a high power factor type (over 90%) rated for operation at -20°F (-29°C) or lower and under a +10% line voltage variation with minimal change (+4% max.) in lumen output. A regulator or reactor ballast should be furnished for high pressure sodium luminaires; a reactance type ballast will be acceptable for low pressure sodium units.

The appropriate lamp shall be furnished with each unit - 250Q/CL for the quartz iodine luminaires, LU70 for the H. P. S., and 50X35 for the LPS units.



The unit should have photometric characteristics as indicated in the applicable candlepower table with an illumination pattern similar to that shown by the isofootcandle curves (see Note 2) when operated at rated voltage of 120V nominal.

NOTES:

- Catalog literature and photometric data shall be submitted to the Contracting Officer on proposed luminaires (including "test luminaires"). The preferred format for photometric data is the candlepower table. The luminaire must have been tested in accordance with IES procedures and with readings taken at no more than 45° intervals (10° preferred). The data should identify the lamp number, lumen rating, test date, and test format (horizontal polar axis or vertical polar axis). If the candlepower test data lists values only for one horizontal and one vertical position (one plane and one cone), additional photometric data in the form of illumination curves (isofootcandle charts) or illumination grids (footcandle printouts) is to be included. If illumination data represents maintained levels rather than initial, the appropriate parameters such as lamp lumen depreciation, dirt factor, group relamping interval, etc. (see "Design Luminaire" data) should be noted.
- It was necessary to utilize a specific manufacturer's fixture in making calculations and establishing reference illumination grids and charts. Any other unit which conforms to the specifications listed and has similar photometric characteristics will be acceptable. To be considered equivalent, the average value of candlepower must be within 10% of the average listed on this sheet for the corresponding luminaire or the average illumination should be 90% or more of the average shown on the illumination charts on sheet E.5.
- The illumination charts shown on Sh. E.5 portray the distribution patterns applicable to the specific luminaires listed in the "Design Luminaire" data. The solid curves identify the illumination levels that will be projected 6 inches above ground from a single luminaire mounted 15 feet above reference grade, considered on a horizontal measurement basis. The values above the curves denote the illumination levels existing when the unit is initially installed; the figures in parenthesis below the curves are the corresponding values of maintained illumination (see "Design Luminaire" data). The dashed lines represent resultant conditions when the mounting height is lowered to 13 feet (illumination values are identical for corresponding dashed and solid curves).
- The illumination grid on Sh. E.5 was calculated using the two-luminaire arrangement illustrated on that sheet. Figures at grid points represent maintained values of horizontal illumination. The figures shown above curves are initial values.
- Reference grade for mounting heights and photometric data is equivalent to the bottom of the door opening and the interior floor level.
- Spare lamps in an amount equal to not less than 5% of the total luminaires installed shall be furnished in packaging recommended by the manufacturer for storage.
- Dimensions listed in feet can be converted to meters by applying the multiplier of 3.048. Footcandle values will read in lux if a 10.76 multiplier is applied.
- If higher wattage luminaires should be required in special cases, the HPS curves could be adapted, with moderate accuracy, for use with 100W units (9500 lumens) or 150W (16000 lumens) by applying a multiplier of 1.6 or 2.8 respectively. The LPS curves would be valid for a 55W (8000 lumens) unit if a multiplier 1.7 were applied.
- The wiring table on Sh. E.2 is based on 3% max. voltage drop in the lines. Actual lumen output of the luminaires will be reduced 1-2% from the levels indicated on the illumination curves for the HPS and LPS sources and approx. 4% for the quartz iodine.

APPLICATION NOTES:



- The designer should select one of the three exterior light options and edit accordingly (delete, modify, or cross out).
- For applications where instant start characteristics are essential, the quartz iodine unit (luminaire "G") should be used. High pressure sodium (HPS) will deliver 50% to 80% of rated illumination in one minute (varies with mfr., temperature, etc.), approx. 95% in two minutes. The low pressure sodium unit will deliver 50% output in approx. 4 minutes, 95% in approx. 7 minutes. Restrike to full output is instantaneous with quartz, essentially so for LPS (if outage is 2 min. or less), but approx. 4 min. for HPS.
- Color discrimination suffers somewhat under HPS light, but virtually disappears under LPS unless light from another source (such as interior lights, is present. Contribution from a separate source amounting to 10% of the LPS light level is sufficient to restore color rendition. If accurate color discrimination is critical, use the quartz luminaire.
- If the above characteristics are not critical, the more energy efficient LPS or HPS units should be used in lieu of the quartz type. The HPS unit is preferred in the absence of other instructions.




THIS PLAN ACCOMPANIES CONTRACT NO. DAC445 MODIFICATION NO.

DATE	DESCRIPTION	MADE	APPROD
REVISIONS			
U. S. ARMY ENGINEER DISTRICT, OMAHA CORPS OF ENGINEERS OMAHA, NEBRASKA			
DESIGNED BY: DLV	MUNITION STORAGE IGLOOS MAGAZINE, STRADLEY TYPE (30'-0" SPAN) EARTH COVERED EXTERIOR ELECTRICAL SHEET 1		
DRAWN BY: TSA	347-78-48 (36)		
CHECKED BY:	33-15-03		
SUBMITTED BY:	DRAWING NUMBER		
CHIEF ELEC. FAC. SECTION	SHEET E-4		
RECOMMENDED:	APPROVED:		
CHIEF DESIGN BRANCH	CHIEF ENGINEERING DIVISION		
APPROVED:	SCALE: AS SHOWN SPEC. NO. DAC445		
CGL C. E. DISTRICT ENGINEER		SHEET E-4	

LUMINAIRE "E" - 70W HIGH PRESSURE SODIUM
 STYLE "I" MAINTENANCE FACTOR = 0.7225; AVG. ILLUMINATION = (0.18) 0.25 FC




ILLUMINATION GRID - 70W H.P.S.
 APPLICABLE COMPUTER RUN = TE024; M.H. = 13 ft.
 Average ILLUMINATION = (0.12) 0.17 FC




EXTERIOR LIGHTING MOUNTING LAYOUT

SCALE: 3/32 INCH = 1 FOOT

LUMINAIRE "F" - 35W LOW PRESSURE SODIUM
 STYLE "I" MAINTENANCE FACTOR = 0.90; AVG. ILLUMINATION = (0.11) 0.12 FC



LUMINAIRE "G" - 250W QUARTZ IODINE
 STYLE "I" MAINTENANCE FACTOR = 0.8075; AVG. ILLUMINATION = (0.22) (0.27) FC



MTG. HT.	MULT.	ACTUAL DISTANCE IN FEET										
M.H.	1.0	-50	-40	-30	-20	-10	0	10	20	30	40	50
M.H.	1.5	-60	-48	-36	-24	-12	0	12	24	36	48	60
M.H.	2.0	-75	-60	-45	-30	-15	0	15	30	45	60	75

ISOFOOTCANDLE (ISOLUX) CHARTS
 (SEE NOTE 3; REFERENCE MH = 15 FT. SEE APPLICATION NOTES 1-4)

DESIGN LUMINAIRES
 (See Note 2)

a. Fixture "E"
 Luminaire Type: 70W high pressure sodium wall mount unit, Model SWP 465
 Manufacturer: Holophane Catalog No: 419-20
 Computer Code: V070SXXH01 Lamp No: LU70
 Group Relamping: 8000 hrs. at 20% failure Input Watts: 95
 Initial Lumens: 5800 Rated Life in Hours: 12000
 Dirt Factor: 0.85 Lumen Depreciation Factor: 0.85
 Eff. Projected Area (EPA): 1.1 sq. ft. Weight: 18 lb.

Date: Approx. 1975 Type: Candlepower Table (computer printout)
 I. D. No: 27914 Socket Position: NA Multiplier: 1.0



b. Fixture "F"
 Luminaire Type: 35W low pressure sodium wall mount unit
 Manufacturer: Norelco Catalog No: 33830
 Computer Code: V35WL4MNO1 Lamp No: SOX35
 Group Relamping: 14000 hrs. at 20% failure Input Watts: 60 - 67*
 Initial Lumens: 4800 Rated Life in Hours: 18000
 Dirt Factor: 0.90 Lumen Depreciation Factor: 1.00
 Eff. Projected Area (EPA): 1.10 sq. ft. Weight: 20 lb.

Date: January 18, 1977 Type: Candlepower Table
 I. D. No: ERL 2080 Socket Position: NA Multiplier: 1.0

c. Fixture "G"
 Luminaire Type: 250W tungsten-halide wall-mount; Wall packette
 Manufacturer: Holophane Catalog No: 414
 Computer Code: V250QXXH01 Lamp No: 250Q/CL
 Group Relamping: 1600 hrs. at 20% failure Input Watts: 250
 Initial Lumens: 5000 Rated Life in Hours: 2000
 Dirt Factor: 0.85 Lumen Depreciation Factor: 0.95
 Eff. Projected Area (EPA): 1.10 sq. ft. Weight: 12 lb.

Date: March 18, 1966 Type: Candlepower Table/Graph (45° plane - 77° cone)
 I. D. No: 21495-L Socket Position: NA Multiplier: 1.0


* Wattage at 8000 Hours




CONVERSION GRAPHS

FOOTCANDLE MULTIPLIER FOR ALTERNATE MTG. HTS.


MOUNTING HEIGHT	MULTIPLIER
30	0.25
25	0.36
20	0.56
15	1.00
13	1.33
12	1.56
10	2.25
8	3.52
5	9.00




SECTION C-C
 SCALE: 1 INCH = 2 FEET




DATE	DESCRIPTION	MADE	APPROV
REVISIONS			
U. S. ARMY ENGINEER DISTRICT, OMAHA CORPS OF ENGINEERS OMAHA, NEBRASKA			
DESIGNED BY: D.L.V.	DATE: 347-78-48(37)		
DRAWN BY: T.S.A.	SPEC. NO. DCA445		
CHECKED BY:	DRAWING NUMBER 33-15-03		
SUBMITTED BY:	SHEET E-5		
CHIEF ELEC. FAC. SECTION	APPROVED:	CHIEF ENGINEERING DIVISION	SCALE: AS SHOWN
RECOMMENDED:	CHIEF DESIGN BRANCH	COL. C. E., DISTRICT ENGINEER	
THIS PLAN ACCOMPANIES CONTRACT NO. DCA445 MODIFICATION NO.			




SECTION 1
S-3|S-4
SCALE: 3/8 INCH = 1 FOOT




SECTION 2
S-3|S-4
SCALE: 3/8 INCH = 1 FOOT




SECTION 3
S-3|S-4
SCALE: 3/8 INCH = 1 FOOT




SECTION 4
S-3|S-4
SCALE: 3/8 INCH = 1 FOOT



SECTION 5
S-3|S-4
SCALE: 1/2 INCH = 1 FOOT




SECTION 6
SCALE: 3/8 INCH = 1 FOOT




SECTION 7
SCALE: 3/8 INCH = 1 FOOT

TABLE I	
BAR SIZE	LAP (INCHES)
#4	20
#6	31
#8	51
#9	65




SECTION 8
S-3|S-4
SCALE: 3/8 INCH = 1 FOOT




SECTION 9
S-3|S-4

SECTION 10
S-3|S-4
SCALE: 1/2 INCH = 1 FOOT


DATE	DESCRIPTION	MADE	APPROD
Dec. 80	Revised		B.N.H. C.O.E.
REVISIONS			
U. S. ARMY ENGINEER DISTRICT, OMAHA CORPS OF ENGINEERS OMAHA, NEBRASKA			
DESIGNED BY: B.N.H.	MUNITION STORAGE IGLOOS MAGAZINE, STRADLEY TYPE (30'-0" SPAN) EARTH COVERED PORTAL WALL SECTIONS		
DRAWN BY: J.L.R./A.J.A.	APPROVED: <i>[Signature]</i> DATE: MARCH 1979		
CHECKED BY: J.B.G. JR.	CHIEF ENGINEERING DIVISION		
SUBMITTED BY: <i>[Signature]</i>	RECOMMENDED: <i>[Signature]</i>		
CHIEF BLDGS. SECTION	CHIEF DESIGN BRANCH		
APPROVED: <i>[Signature]</i>	SCALE: AS SHOWN		
THIS PLAN ACCOMPANIES CONTRACT NO. DACA45		MODIFICATION NO.	
DRAWING NUMBER 33-15-03		SHEET S-4	




GENERAL NOTES:
 1. For details of door frame and door sill, see sheet S-5.
 2. For location of conduit to be in place when concrete is placed, see sheet E-1.



See Designer note 1
 Note: Bars shown are for rear face. Continue front face bars full height of wall.





DETAIL A
 SCALE: 1/2 INCHES = 1 FOOT
 12" 9" 6" 3" 0"



DETAIL B
 SCALE: 1/2 INCHES = 1 FOOT
 12" 9" 6" 3" 0"

Designer Notes:

- The minimum footing depth shall be 4'-2" below finished grade. Depth of footings will be increased if required by soil or frost conditions.
- At designers option, arch footings shall extend to full frost penetration depth, or provide non-frost-susceptible material under arch footings to full depth of frost penetration.
- Footings are sized for a soil bearing pressure of 3500 P.S.F.
- $D = 1.25 (W^{1/2})$
 D = Minimum separation in feet
 1.25 = Constant
 W = Equivalent weight of TNT in pounds
- Footing design loads
 a) Dynamic axial load (P) = +48 Kips
 b) Dynamic moment (M) = +1878 Kip-in
 c) Static axial load (P) = +14 Kips
 d) Static moment (M) = +128 Kip-in
- Allowable dynamic soil bearing pressure for static loading plus dynamic loading is 3 times the allowable soil bearing pressure



DATE	DESCRIPTION	MADE	APPROD
Dec 80	Revised		

REVISIONS

**U. S. ARMY ENGINEER DISTRICT, OMAHA
 CORPS OF ENGINEERS
 OMAHA, NEBRASKA**


DESIGNED BY: B.N.H.
 DRAWN BY: S.A.M.-A.J.A.
 CHECKED BY: J.B.G. JR.
 SUBMITTED BY: W.M. Rankin
 CHIEF BLDGS. SECTION
 RECOMMENDED: C. Cumber
 CHIEF DESIGN BRANCH
 APPROVED: R. J. [Signature]
 CHIEF ENGINEERING DIVISION

DATE: MARCH 1979


SCALE: AS SHOWN
 SPEC. NO. DACA45
 DRAWING NUMBER
33-15-03
 SHEET S-3

COL. G. E. DISTRICT ENGINEER


THIS PLAN ACCOMPANIES CONTRACT No. DACA45
 MODIFICATION No.




SECTION S-11 S-2
SCALE: 1/2 INCH = 1 FOOT




LOUVER DETAIL
SCALE: 3 INCHES = 1 FOOT




CONSTRUCTION JOINT & GUTTER DETAIL
SCALE: 3/4 INCH = 1 FOOT




ARCH FOOTING DETAIL
NO SCALE



DETAIL E
S-31 S-2
SCALE: 3 INCHES = 1 FOOT



DETAIL F
S-31 S-2
SCALE: 1 1/2 INCHES = 1 FOOT






DETAIL G
S-31 S-2
SCALE: 3 INCHES = 1 FOOT

DATE	DESCRIPTION	MADE	APPROD
Dec 80	Revised		



REVISIONS			
NO.	DESCRIPTION	DATE	BY

U. S. ARMY ENGINEER DISTRICT, OMAHA CORPS OF ENGINEERS OMAHA, NEBRASKA			
DESIGNED BY: B.N.H.	MUNITION STORAGE IGLOOS MAGAZINE, STRADLEY TYPE (30'-0" SPAN) EARTH COVERED ARCH. & MISC. DETAILS		
DRAWN BY: J.L.R./A.J.A.	APPROVED: <i>[Signature]</i>	DATE: MARCH 1979	
CHECKED BY: J.B.G. JR.	CHIEF ENGINEERING DIVISION		
SUBMITTED BY: <i>[Signature]</i>	SCALE: AS SHOWN	SPEC. NO. DAC445	
CHIEF BLOSS SECTION		DRAWING NUMBER	
RECOMMENDED: <i>[Signature]</i>			
APPROVED: <i>[Signature]</i>			
COL. D. E. DISTRICT ENGINEER			

THIS PLAN ACCOMPANIES CONTRACT NO. DAC445
MODIFICATION NO.



- General Notes:**
1. Lighting protection shall be provided as indicated on sheet E-2. Concrete reinforcing shall be bonded and all embedded metal shall be part of a continuous electrically grounded system.
 2. All concrete shall develop a minimum ultimate compressive strength at the end of 28 days of 4,000 psi.
 3. All reinforcing steel shall be ASTM A615 or A617. All reinforcing steel shall be grade 60.
 4. Reinforcing splices shall be in accordance with current ACI Standard 318 unless otherwise indicated on the drawings.



THIS PLAN ACCOMPANIES CONTRACT No. DACA45 MODIFICATION NO.

REVISIONS		DATE	DESCRIPTION	MADE	APPROV
Dec 80	Revised			BNH	G.C.B.

**U. S. ARMY ENGINEER DISTRICT, OMAHA
CORPS OF ENGINEERS
OMAHA, NEBRASKA**

DESIGNED BY: B.N.H.	MUNITION STORAGE IGLOOS MAGAZINE, STRADLEY TYPE (30'-0" SPAN) EARTH COVERED DRAINAGE PLAN, SECTION, AND MISC. DETAILS	DATE: MARCH 1979
DRAWN BY: S.A.M.-A.J.A.		SCALE: AS SHOWN
CHECKED BY: J.B.G. JR.		SPEC. NO. DACA45
SUBMITTED BY: [Signature]		DRAWING NUMBER
RECOMMENDED BY: [Signature]	APPROVED: [Signature]	33-15-03
CHIEF DESIGN BRANCH	CHIEF ENGINEERING DIVISION	SHEET S-1